

OFFER FORM ACTED Libya

Date: التاريخ _____ (to be indicated by the bidder)

Tender N°: عدد المناقص: T/14DPE/H94/QIP/BENHAZI/PRG/10062019/001

To be Filled by Bidder (COMPULSORY)

Details of Bidding Company t/ تفاصيل الشركة المتقدمة

1. Company Name / اسم الشركة (_____)
2. Company Authorized Representative Name / اسم الشخص المفوض (_____)
3. Company Registration No / رقم السجل القانوني للشركة (_____)
No/Country/ Ministry
4. Company Specialization / تخصص الشركة (_____)
5. Mailing Address / عنوان البريد (_____)
Country/Governorate/City/St name/Shop-Office No
- a. Contact Numbers / رقم الاتصال (Land Line: _____ / Mobile No: _____)
- b. E-mail Address / البريد الالكتروني (_____)

I undersigned _____, agree to provide ACTED, non-profit NGO, with items answering the following specifications, according to the general conditions and responsibilities that I engage myself to follow.

انا الموقع ادناه ----- اوافق على تزويد أكتد المنظمة الغير حكومية والغير ربحية بهذه البنود لتتلقى المواصفات التالية وفقا للشروط العامة والمسؤوليات التي وافقت عليها بنفسى.

PLEASE FILL IN THE FOLLOWING TABLES (ONE OR MORE)

- **NOTE: BIDDERS CAN BID FOR ONE, TWO, THREE OR FOUR LOT(S) TO BE CONSIDERED ELIGIBLE.**
- **PLEASE NOTE THAT QUANTITIES ARE INDICATIVES AND THAT QUANTITIES MIGHT BE REVISED DURING THE WORK, WITH PREVIOUS CONFIRMATION FROM ACTED.**
- **NO ADDITIONAL WORK WILL BE PAID IF NOT CONFIRMED UPSTREAM BY ACTED ENGINEER.**

LOT 1: REHABILITATION WORKS – AL JAEDI CLINIC – BENHAZI, BENHAZI, LIBYA.

FIELD VISIT POSSIBLE – 13TH JUNE TO 21ST JUNE 2019 – ACCOMPANIED WITH ACTED BENHAZI ENGINEER.

THE OFFER WILL BE SUBMITTED IN LIBYAN DINARS OR USD ALL COST INCLUDED (INCLUDING DELIVERY AND INSTALLATION) AND TAXES INCLUDED.

| Item No. | Item Description | Unit | Quantity | Unit Price LYD VAT Included | TOTAL Price LYD VAT Included | Unit Price USD VAT Included | TOTAL Price USD VAT Included |
|---------------------------|--|----------------|----------|-----------------------------|------------------------------|-----------------------------|------------------------------|
| 1- METAL WORKS | | | | | | | |
| 1,1 | Supply and installing of aluminum partition to divide some departments in the clinic from approved sample of B.S section or equivalent section, rate shall include workmanship and all required materials such as doors, window if necessary, hinges, locks, handle, glass...etc. and all accessories and fittings all according to the work techniques and instruction of the engineer. | M ² | 30 | | | | |
| 1,2 | Fabricate, supply, & install of metal shaded from 3 m long of metal panels and 4mm*4mm*2mm of steel section, rate shall include workmanship and all required materials such as 25*25 CM of cap angles, water drains & painting, all according to the work techniques and instruction of the engineer. | M ² | 45 | | | | |
| 2 - CONCRETE WORKS | | | | | | | |

| | | | | | | | |
|------------------|---|----------------|----|--|--|--|--|
| 2,1 | Supply and pouring of 20 CM thickness of reinforcement concrete floor, rate shall include workmanship, formwork, handling, vibrating, curing...etc and all required materials, average of reinforcement is about 115 KG/M3 pouring of C 30 concrete, concrete shall contain 350 Kg of cement, 0.8 M3 of aggregates and 0.4 M3 of sand all mixed with clean drinkable water, all according to the work techniques and instruction of the engineer. | M ² | 76 | | | | |
| 3-SANITARY WORKS | | | | | | | |
| 3,1 | Supply and installing of 3/4 inches PPR pipes, pipes shall be jointed, fixed & connected from the water tank to the bathroom, rate shall include excavating, backfilling, pavement, materials ,workmanship, all accessories & fittings, all according to the work techniques and instruction of the engineer. | Meter Length | 42 | | | | |
| 3,2 | Supply and installing of Italian flexible hose 50 cm long from approved sample to feed the water boiler for the section of neurology, all according to the work techniques and instruction of the engineer. | Piece | 2 | | | | |
| 3,3 | Supply and installation of 1" or 3/4" buried valves according to the approved sample, for section of neurology, all according to the work techniques and instruction of the engineer. | Piece | 1 | | | | |
| 3,4 | Supply and install of plastic Italian flexible hose (siphone) for hand wash basin rate include, materials, workmanship all accessories & fittings, all according to the work techniques and instruction of the engineer. | Piece | 1 | | | | |
| 3,5 | supply and install of Italian made water mixer tap for the hand wash basin, for section of neurology, according to the approved sample, all according to the work techniques and instruction of the engineer. | Piece | 1 | | | | |

| | | | | | | | |
|------|--|--------------|---|--|--|--|--|
| 3,6 | Supply and installing of water boiler 40 liter capacity from approved sample, rate includes all accessories such as water heater switch, wiring...etc, all according to the work techniques and instruction of the engineer. | Piece | 1 | | | | |
| 3,7 | Supply and installation of angle valves according to the approved sample, for section of neurology, all according to the work techniques and instruction of the engineer. | Piece | 4 | | | | |
| 3,8 | supply and install of sewers with size of 15*15 cm complete with the cover and from the approved sample for toilets sewerage and all accessories all according to the work techniques and instruction of the engineer. | Piece | 1 | | | | |
| 3,9 | Supply and installing of 2 inch drain pipe from approved sample such as smart or red sea, to drain the sewerage from room hand wash basin to the existing manholes, rate shall include all needed work such as excavating, backfilling, paving & all accessories & fittings, all according to the work techniques and instruction of the engineer. | Meter Length | 3 | | | | |
| 3,10 | Supply and installing of 4 inch drain pipe from approved sample such as smart or red sea, to drain the sewerage from container's WC to the existing manholes, rate shall include all needed work such as excavating, backfilling, paving & all accessories & fittings, all according to the work techniques and instruction of the engineer. | Meter Length | 4 | | | | |

| | | | | | | | |
|---------------------------|--|----------------|----|--|--|--|--|
| 3,11 | Supply and installing of 6 inch drain pipe from approved sample such as smart or red sea, to drain the sewerage from container's WC to the existing manholes, rate shall include all needed work such as excavating, backfilling, paving & all accessories & fittings, all according to the work techniques and instruction of the engineer. | Meter Length | 28 | | | | |
| 3,12 | supplying and carrying out of manhole with size of 80* 80 Cm and varies depth according to the sloping completely with cover, rate shall include materials, workmanship, all according to the work techniques and instruction of the engineer. | Piece | 3 | | | | |
| 4-PAINTING WORKS | | | | | | | |
| 4,1 | Supply and painting using emulsion for internal walls with weather shield paint of white color and from approval product, painting shall apply by one coat of primer, two coats of approved paints using putty before, preparation of surface, smoothing, knotting, stepping, protection of floor, doors, windows...etc, all according to the work techniques and instruction of the engineer. | M ² | 54 | | | | |
| 5-ELECTRICAL WORKS | | | | | | | |
| 5,1 | Supplying and replace of outdoor led lamps 60 watt completely with the cover from approval sample, rate shall include repairing of any default of the lighting poles, all according to the work techniques and instruction of the engineer. | Piece | 30 | | | | |
| 5,2 | Supply and installing 12 MM crossing section of electrical copper cable according to applicable standards and specifications, rate shall include excavation, backfilling, tubing & pavement, all according to the work techniques and instruction of the engineer. | Meter Length | 15 | | | | |

| 6-CERAMIC WORKS | | | | | | | |
|---|---|----------------|----|---------------|--|---------------|--|
| 6,1 | Supply and install of ceramic floor tiles (anti slip) and wall tiles for one room to be as section of neurology, from approval sample. Rate shall include removing of existing tiles, workmanship & skirting, all required materials, All according to the work techniques and instruction of the engineer. | M ² | 15 | | | | |
| GRAND TOTAL (including all applicable taxes and delivery and installation) | | | | In LYD | | In USD | |

BIDDER'S COMMENTS/REMARKS:

1. _____
2. _____

DELIVERY CONDITIONS GUARANTEED BY THE BIDDER :

..... Days for 50% of completion of works
 Days for 100% of completion of works

BIDDER'S TERMS AND CONDITIONS:

1. Valid of the offer: _____ (recommended: 6 months (for selection and contract's signature).
2. Terms of delivery: _____ (recommended: DDP)
3. Terms of payment: _____
4. Payments deadline: _____ days after invoice validated



T/14DPE/H94/QIP/BENHAZI/PRG/10062019/001

Reminder: The offer will be submitted in English and in Libyan Dinars or USD all cost included (including delivery and installation) and taxes included.

- a. Bidders shall comply with all valid Government legal Documentation and adhere to Regulations to operate in Libya such as being regular tax payer to offer such goods and services as specified in the tender
2. An entity established in Libya is considered tax resident in Libya.
 - a. Any Income generated in Libya from work performed therein should be subject to income tax in Libya.
 - b. The supplier will have the obligation to provide Tax information, including handling the preparation, filing, and stamping of federal, state, or national body on the invoice of the performed service/work.

Name of Bidder's Authorized Representative: _____

Authorized signature and stamp: _____

Date: _____

.....

LOT 2: REHABILITATION WORKS –BODRISA SCHOOL – BENGHAZI, BENGHAZI, LIBYA.

FIELD VISIT POSSIBLE – 13TH JUNE TO 21ST JUNE 2019 – ACCOMPANIED WITH ACTED BENGHAZI ENGINEER.

THE OFFER WILL BE SUBMITTED IN LIBYAN DINARS OR USD ALL COST INCLUDED (INCLUDING DELIVERY AND INSTALLATION) AND TAXES INCLUDED.

| Item No. | Item Description | Unit | Quantity | Unit Price LYD VAT Included | TOTAL Price LYD VAT Included | Unit Price USD VAT Included | TOTAL Price USD VAT Included |
|---------------------------------|---|----------------|----------|-----------------------------|------------------------------|-----------------------------|------------------------------|
| 1- METAL AND DOORS WORKS | | | | | | | |
| 1,1 | Repairing and maintaining of aluminium windows, repairing the existing shall made out by replacing and reinstalling of any damaged parts of the aluminium or hinges, locks,handle, rubber, glasses...etc, all according to the work techniques and instruction of the engineer. | M ² | 15 | | | | |
| 1,2 | Fabricate, supply, & install of metal goal keeper bars size approximately 3*2m, of 3" metal tubing thickness 2.5 mm, work shall include all required materials, workmanship& painting which shall be made by smoothing, cleaning, one coat of primer and two coats of approved reflective white color paint and color, rate shall include the net of the goal keeper, and all accessories all according to the work techniques and instruction of the engineer. | Piece | 2 | | | | |

| | | | | | | | |
|------------------------------------|---|--------------|---|--|--|--|--|
| 1,3 | Fabricate, supply, & install of metal volleyball 1.5 m high bars using of 3" metal tubing thickness 2.5 mm, work shall include all required materials, workmanship& painting which shall be made by smoothing, cleaning, one coat of primer and two coats of approved reflective white color paint and color, rate shall include the net, and all accessories all according to the work techniques and instruction of the engineer. | Piece | 2 | | | | |
| 1,4 | Fabricate, supply, & install of basketball board similiar to the existing, the work shall include all required materials, workmanship& painting which shall be made by smoothing, cleaning, one coat of primer and two coats of approved reflective white color paint , rate shall include the net of the basket, and all accessories all according to the work techniques and instruction of the engineer. | Piece | 2 | | | | |
| 1,5 | Repairing of wooden doors with the fram, the repairing shall made by cutting off the damage parts and replacing them with new wooden parts, fixing shall made by nails and gluing the new parts with old parts, removing old paint adding wooden paste to hide any defects, rate shall include hinges, locks, handle, glass...etc, and all accessories all according to the work techniques and instruction of the engineer. | Piece | 6 | | | | |
| 2- MARBLE and CERAMIC WORKS | | | | | | | |
| 2,1 | Supply and installing 120*30 mm thick of marble for windows of the toilets, rate shall include workmanship and all required materials all according to the work techniques and instruction of the engineer. | Meter Length | 5 | | | | |

| | | | | | | | |
|-------------------|--|----------------|----|--|--|--|--|
| 2,2 | Supply and install of ceramic floor tiles (anti slip) and wall tiles for toilets, from approval sample. Rate shall include removing of existing tiles, workmanship & skirting, all required materials, All according to the work techniques and instruction of the engineer. | M ² | 24 | | | | |
| 3- PAINTING WORKS | | | | | | | |
| 3,1 | Supply and painting using emulsion for internal walls of the toilets with weather shield paint of white color and from approval product, painting shall apply by one coat of primer, two coats of approved paints using putty before, preparation of surface, smoothing, knotting, stepping, protection of floor, doors, windows...etc, all according to the work techniques and instruction of the engineer. | M ² | 95 | | | | |
| 3,2 | In lump sum supply and paint of the playground yard using of reflected white oil paint from approval product such as JOTUN, DELUX or equivalent product, to meet the standard requirement of football and volleyball both at the same pitch and basketball pitch, painting shall apply by using of painting tapes to ensure the straightness of painting line, cleaning well before painting.....etc., all according to the work techniques and instruction of the engineer. | Lump Sum | 1 | | | | |
| 4- SANITARY WORKS | | | | | | | |
| 4,1 | Supply and installing of 3/4 inches PPR pipes, pipes shall be jointed, fixed & connected from the water tank to the toilets, rate shall include excavating, backfilling, pavement, materials, workmanship, all accessories & fittings, all according to the work techniques and instruction of the engineer. | Meter Length | 50 | | | | |

| | | | | | | | |
|-----|---|-------|----|--|--|--|--|
| 4,2 | Supply and replace of 2 HP water submersible pump (SAER) or equivalent product, rate include materials, workmanship all accessories & fittings, all according to the work techniques and instruction of the engineer. | Piece | 1 | | | | |
| 4,3 | Supply and installing of 2 HP water centrifugal pump (SAER or DAM) or equivalent product, rate include materials workmanship, all accessories & fittings, all according to the work techniques and instruction of the engineer. | Piece | 1 | | | | |
| 4,4 | Supply and installation of Italian flexible hose with sprayer & angle valve for toilets and replacing the existing, all according to the work techniques and instruction of the engineer. | Piece | 15 | | | | |
| 4,5 | Supply and installing of complete package of toilets box drain (flasher) from approved sample, and all accessories and fittings, all according to the work techniques and instruction of the engineer. | Piece | 10 | | | | |
| 4,6 | Supply and installation of toilet seats cover according to the approved sample, all according to the work techniques and instruction of the engineer. | Piece | 10 | | | | |
| 4,7 | Supply and installing of Italian flexible hose 50 cm long from approved sample to feed toilets, basins, water boiler and replacing the existing, all according to the work techniques and instruction of the engineer. | Piece | 18 | | | | |
| 4,8 | Supply and installation of 1" buried valves according to the approved sample, all according to the work techniques and instruction of the engineer. | Piece | 4 | | | | |
| 4,9 | Supply and installing of toilets from approved sample with dual flush, capacity of 10 liter, rate includes seat cover with stainless steel hinges, and all accessories, all according to the work techniques and instruction of the engineer. | Piece | 2 | | | | |

| | | | | | | | |
|------|--|--------------|----|--|--|--|--|
| 4,10 | Supply and installing of water boiler 80 liter capacity from approved sample, rate includes all accessories, all according to the work techniques and instruction of the engineer. | Piece | 2 | | | | |
| 4,11 | Supply and installation of angle valves according to the approved sample, all according to the work techniques and instruction of the engineer. | Piece | 15 | | | | |
| 4,12 | Supply and install of Italian made water mixer tap for the shower and the kitchen according to the approved sample, all according to the work techniques and instruction of the engineer. | Piece | 2 | | | | |
| 4,13 | Supply and install of sewers with size of 15*15 cm complete with the cover and from the approved sample for toilets sewerage and all accessories, all according to the work techniques and instruction of the engineer. | Piece | 3 | | | | |
| 4,14 | Supply and install of Italian made water mixer tap for hand wash basin according to the approved sample, all according to the work techniques and instruction of the engineer. | Piece | 14 | | | | |
| 4,15 | Supply and install of plastic Italian flexible hose (siphone) for hand wash basin rate include, materials, workmanship all accessories & fittings, all according to the work techniques and instruction of the engineer. | Piece | 4 | | | | |
| 4,16 | Supply and installing of 4 inch drain pipe from approved sample such as smart or red sea, to drain the sewerage from container's bathroom to the existing manholes & to change of some existing, rate shall include all needed work such as excavating, backfilling, paving & all accessories & fittings all according to the work techniques and instruction of the engineer. | Meter Length | 24 | | | | |

| | | | | | | | |
|----------------------------|---|--------------|----|--|--|--|--|
| 4,17 | Supply and installing of 6 inch drain pipe from approved sample such as smart or red sea, to drain the sewerage from container's WC to the existing manholes, rate shall include all needed work such as excavating, backfilling, paving & all accessories & fittings all according to the work techniques and instruction of the engineer. | Meter Length | 40 | | | | |
| 4,18 | Supplying and carrying out of manhole with size of 80* 80 Cm and varies depth according to the sloping completely with cover, rate shall include materials, workmanship, all according to the work techniques and instruction of the engineer. | Piece | 5 | | | | |
| 4,19 | Cleaning and draining of internal and external sewerage system rate shall include any closed parts, all according to the work techniques and instruction of the engineer. | Meter Length | 50 | | | | |
| 5- ELECTRICAL WORKS | | | | | | | |
| 5,1 | Supply and installing 12 MM crossing section of electrical copper cable for the container according to applicable standards and specifications, rate shall include excavation, backfilling, tubing & pavement, all according to the work techniques and instruction of the engineer. | Meter Length | 50 | | | | |
| 5,2 | Supplying and installation of fluorescent lights 4*60 w, 60 cm long complete with cover, Philips or equivalent type, rate including all needed materials and workmanship, all according to the work techniques and instruction of the engineer. | Piece | 10 | | | | |
| 5,3 | Supplying and replace economic spotlight lamps 65 watt, all according to the work techniques and instruction of the engineer. | Piece | 16 | | | | |



| | | | | | | | |
|---|---|-------|---|---------------|--|---------------|--|
| 5,4 | Supply and installing of 20 A electrical sockets with three pins for water heater and 16 A switches for lighting ABB or equivalent product and for lighting controlling, and replacing of the existing, rate shall include all necessary materials such as wiring, box, breakers...etc, all according to the work techniques and instruction of the engineer. | Piece | 6 | | | | |
| GRAND TOTAL (including all applicable taxes and delivery and installation) | | | | In LYD | | In USD | |

BIDDER'S COMMENTS/REMARKS:

- 3. _____
- 4. _____

DELIVERY CONDITIONS GUARANTEED BY THE BIDDER :

..... Days for 50% of completion of works
 Days for 100% of completion of works

BIDDER'S TERMS AND CONDITIONS:

- 5. Valid of the offer: _____ (recommended: 6 months for selection and contract's signature).
- 6. Terms of delivery: _____ (recommended: DDP)
- 7. Terms of payment: _____
- 8. Payments deadline: _____ days after invoice validated

Note: The offer will be submitted in English and in Libyan Dinars or USD all cost included (including delivery and installation) and taxes included.
 a. Bidders shall comply with all valid Government legal Documentation and adhere to Regulations to operate in Libya such as being regular tax payer to offer such goods and



T/14DPE/H94/QIP/BENHAZI/PRG/10062019/001

services as specified in the tender

3. An entity established in Libya is considered tax resident in Libya.
 - a. Any Income generated in Libya from work performed therein should be subject to income tax in Libya.
 - b. The supplier will have the obligation to provide Tax information, including handling the preparation, filing, and stamping of federal, state, or national body on the invoice of the performed service/work.

Name of Bidder's Authorized Representative: _____

Authorized signature and stamp: _____

Date: _____



LOT 3: REHABILITATION WORKS – BUTANI CLINIC – BENGHAZI, BENGHAZI, LIBYA.

FIELD VISIT POSSIBLE – 13TH JUNE TO 21ST JUNE 2019 – ACCOMPANIED WITH ACTED BENGHAZI ENGINEER.

THE OFFER WILL BE SUBMITTED IN LIBYAN DINARS OR USD ALL COST INCLUDED (INCLUDING DELIVERY AND INSTALLATION) AND TAXES INCLUDED.

| Item No. | Item Description | Unit | Quantity | Unit Price LYD VAT Included | TOTAL Price LYD VAT Included | Unit Price USD VAT Included | TOTAL Price USD VAT Included |
|--------------------------|---|----------------|----------|-----------------------------------|------------------------------------|--------------------------------------|---------------------------------------|
| 1- CONCRETE WORKS | | | | | | | |
| 1,1 | Supply and pouring of 20 CM thickness of reinforcement concrete floor, rate shall include workmanship, formwork, handling, vibrating, curing...etc and all required materials, average of reinforcement is about 115 KG/M3 pouring of C 30 concrete, concrete shall contain 350 Kg of cement, 0.8 M3 of aggregates and 0.4 M3 of sand all mixed with clean drinkable water, all according to the work techniques and instruction of the engineer. | M ² | 110 | | | | |
| 2- METAL WORKS | | | | | | | |
| 2,1 | Fabricate, supply and install of metal towers with size of 1.8*1.8 M with height of 3 M to be used for water tanks, the work shall include all required materials, workmanship, fabricating shall be made out by using 50*50*2.5 MM cross section of steel, painting shall be made by smoothing, cleaning, one coat of primer and two coats of approved paint and color, all according to the work techniques and instruction of the engineer. | Piece | 1 | | | | |
| 3- SANITARY WORKS | | | | | | | |

| | | | | | | | |
|-----|---|--------------|----|--|--|--|--|
| 3,1 | Supply and installing 1 inches PPR pipes, pipes shall be jointed, fixed & connected to the water tanks, rate shall include excavating, backfilling, pavement, materials, workmanship, all accessories & fittings, all according to the work techniques and instruction of the engineer. | Meter Length | 25 | | | | |
| 3,2 | Supply and installing of 3/4 inches PPR pipes, pipes shall be jointed, fixed & connected from the water tank to the bathrooms of the container, rate shall include excavating, backfilling, pavement, materials, workmanship, all accessories & fittings, all according to the work techniques and instruction of the engineer. | Meter Length | 20 | | | | |
| 3,3 | Supply and installing of 1 HP water centrifugal pump (SAER or DAM) or equivalent product, rate include, materials, workmanship & wiring, all according to the work techniques and instruction of the engineer. | Piece | 2 | | | | |
| 3,4 | Supply and installing water tank with 3000 liter capacity made from P.V.C from approved sample, rate includes, workmanship, all accessories and fittings, pipe, valves, automatic timer, floater, all according to the work techniques and instruction of the engineer. | Piece | 1 | | | | |
| 3,5 | Supply and installing of 4 inch drain pipe from approved sample such as smart or red sea, to drain the sewerage from container's W C to the existing manholes, rate shall include all needed work such as excavating, backfilling, paving & all accessories & fittings, all according to the work techniques and instruction of the engineer. | Meter Length | 3 | | | | |
| 3,6 | Supply and installing of 6 inch drain pipe from approved sample such as smart or red sea, to drain the sewerage from container's W C to the existing manholes, rate shall include all needed work such as excavating, backfilling, paving & all accessories & fittings, all according to the work techniques and instruction of the engineer. | Meter Length | 28 | | | | |
| 3,7 | supplying and carrying out of manhole with size of 80* 80 Cm and varies depth according to the sloping completely with cover, rate shall include materials, workmanship, all according to the work techniques and instruction of the engineer. | Piece | 4 | | | | |

| 4- ELECTRICAL WORKS | | | | | | | |
|---|--|--------------|----|---------------|--|---------------|--|
| 4,1 | Supply and installing 12 MM crossing section of electrical copper cable according to applicable standards and specifications, rate shall include excavation, backfilling, tubing & pavement, all according to the work techniques and instruction of the engineer. | Meter Length | 30 | | | | |
| GRAND TOTAL (including all applicable taxes and delivery and installation) | | | | In LYD | | In USD | |

BIDDER'S COMMENTS/REMARKS:

5. _____
6. _____

DELIVERY CONDITIONS GUARANTEED BY THE BIDDER :

..... Days for 50% of completion of works
 Days for 100% of completion of works

BIDDER'S TERMS AND CONDITIONS:

1. Valid of the offer: _____ (recommended: 6 months for selection and contract's signature).
2. Terms of delivery: _____ (recommended: DDP)
3. Terms of payment: _____
4. Payments deadline: _____ days after invoice validated

Note: The offer will be submitted in English and in Libyan Dinars or USD all cost included (including delivery and installation) and taxes included.

- a. Bidders shall comply with all valid Government legal Documentation and adhere to Regulations to operate in Libya such as being regular tax payer to offer such goods and services as specified in the tender
4. An entity established in Libya is considered tax resident in Libya.
 - a. Any Income generated in Libya from work performed therein should be subject to income tax in Libya.



T/14DPE/H94/QIP/BENHAZI/PRG/10062019/001

b. The supplier will have the obligation to provide Tax information, including handling the preparation, filing, and stamping of federal, state, or national body on the invoice of the performed service/work.

Name of Bidder's Authorized Representative: _____

Authorized signature and stamp: _____

Date: _____



LOT 4: REHABILITATION WORKS – LATHAMA HEALTH UNIT – BENGHAZI, BENGHAZI, LIBYA.

FIELD VISIT POSSIBLE – 13TH JUNE TO 21ST JUNE 2019 – ACCOMPANIED WITH ACTED BENGHAZI ENGINEER.

THE OFFER WILL BE SUBMITTED IN LIBYAN DINARS OR USD ALL COST INCLUDED (INCLUDING DELIVERY AND INSTALLATION) AND TAXES INCLUDED.

| Item No. | Item Description | Unit | Quantity | Unit Price LYD VAT Included | TOTAL Price LYD VAT Included | Unit Price USD VAT Included | TOTAL Price USD VAT Included |
|--|--|----------------|----------|-----------------------------|------------------------------|-----------------------------|------------------------------|
| 1- (DEMOLISH, REMOVING & PREPARATION) WORKS | | | | | | | |
| 1,1 | Demolish and removal of temporary building, and dumping the disposal materials at main disposal area, all according to the work techniques and instruction of the engineer. | Lump Sum | 1 | | | | |
| 2- CONCRETE WORKS | | | | | | | |
| 2,1 | Supply and pouring of 10 CM thickness of to extend the yard to fit for container of 6*7.5 M, concrete shall contain 250 Kg of cement, 0.8 M3 of aggregates and 0.4 M3 of sand all mixed with clean drinkable water the rate shall include excavation, formwork, handling, vibrating, curing, adjustment of the existing concrete...etc. all according to the work techniques and instruction of the engineer | M ² | 30 | | | | |
| 3- BUILDING WORKS | | | | | | | |
| 3,1 | Supply and building of walls from cement hollow bricks size 20, for the toilets the rate shall including of reinforcement sills for windows and door,all according to the work techniques and instruction of the engineer. | M ² | 65 | | | | |
| 4- PLASTERING WORKS | | | | | | | |

| | | | | | | | |
|--|--|----------------|-----|--|--|--|--|
| 4,1 | Supply and carry out of one layer of plaster for internal and external walls rate shall, all according to the work techniques and instruction of the engineer. | M ² | 51 | | | | |
| 5- PAINTING WORKS | | | | | | | |
| 5,1 | Supply and painting using emulsion for internal and external walls of the watch man room and the toilets with weather shield paint of approved color and product, painting shall apply by one coat of primer, two coats of approved paints using putty before, preparation of surface, smoothing, knotting, stepping, protection of floor, doors, windows...etc, all according to the work techniques and instruction of the engineer. | M ² | 116 | | | | |
| 6- MARBLE and CERAMIC WORKS | | | | | | | |
| 6,1 | Supply and installing 30 mm thick of marble for windows & doors of the watch man room and the toilets, rate shall include workmanship and all required materials all according to the work techniques and instruction of the engineer. | Meter Length | 25 | | | | |
| 6,2 | Supply and install of ceramic floor tiles (anti slip) and wall tiles for the watch man room and toilets, from approval sample. Rate shall including of 10 cm of skirting works, workmanship and all required materials, all according to the work techniques and instruction of the engineer. | M ² | 110 | | | | |
| 7- DOORS, WINDOWS, SUSPENDED CEILING& METAL WORKS | | | | | | | |
| 7,1 | Fabricate, supply, & installation of wooden doors with frame, thickness not less than 40 mm rate shall include four hinges, locks, handle, painting adding wooden paste to hide any defects and all accessories all according to the work techniques and instruction of the engineer. | Piece | 2 | | | | |

| | | | | | | | |
|--------------------------|---|----------------|-----|--|--|--|--|
| 7,2 | Fabricate, supply, & install of metal doors and windows protections for the watch man room, the work shall include all required materials and workmanship, fabricate shall be made out according to the approved shape (decorating), painting shall be made by smoothing, cleaning, one coat of primer and two coats of approved paint and color adding wooden paste to hide any defects, rate shall include four hinges, locks, handle, and all accessories, all according to the work techniques and instruction of the engineer. | M ² | 8,5 | | | | |
| 7,3 | Supply and installing of aluminum windows from approved sample for the watch man room, rate shall include workmanship and all required materials such as hinges, locks, handle, glass...etc. and all accessories and fittings, all according to the work techniques and instruction of the engineer. | M ² | 9 | | | | |
| 7,4 | Supplying and installing of gypsum suspended ceiling, 60*60 of gypsum panel, all according to the work techniques and instruction of the engineer | M ² | 15 | | | | |
| 7,5 | Fabricate, supply, & install of metal shaded from 3 m long of metal panels and 4mm*4mm*2mm of steel section, rate shall include workmanship and all required materials such as 25*25 CM of cap angles, water drains & painting, all according to the work techniques and instruction of the engineer. | M ² | 15 | | | | |
| 7,6 | Fabricate, supply and install of metal towers with size of 1.8*1.8 M with height of 3 M to be used for water tanks , the work shall include all required materials, workmanship, fabricating shall be made out by using 50*50*2.5 MM cross section of steel, painting shall be made by smoothing, cleaning, one coat of primer and two coats of approved paint and color, all according to the work techniques and instruction of the engineer. | Piece | 1 | | | | |
| 8- SANITARY WORKS | | | | | | | |
| 8,1 | Supply and installing 1 inches PPR pipes, pipes shall be jointed, fixed & connected to the water tanks, rate shall include excavating, backfilling, pavement, materials, workmanship, all accessories & fittings, all according to the work techniques and instruction of the engineer. | Meter Length | 31 | | | | |

| | | | | | | | |
|------|--|--------------|----|--|--|--|--|
| 8,2 | Supply and installing of 3/4 inches PPR pipes, pipes shall be jointed, fixed& connected from the water tank to the bathrooms rate shall include excavating, backfilling, pavement, materials, workmanship, all accessories & fittings, all according to the work techniques and instruction of the engineer. | Meter Length | 38 | | | | |
| 8,3 | Supply and installation of 1" buried valves according to the approved sample, all according to the work techniques and instruction of the engineer. | Piece | 3 | | | | |
| 8,4 | Supply and installation of angle valves or PPR valves according to the approved sample, all according to the work techniques and instruction of the engineer. | Piece | 15 | | | | |
| 8,5 | Supply and installation of Italian flexible hose with sprayer for toilets, all according to the work techniques and instruction of the engineer. | Piece | 2 | | | | |
| 8,6 | Supply and installing of Italian flexible hose 50 cm long from approved sample to feed toilets, basins, water boiler, all according to the work techniques and instruction of the engineer. | Piece | 4 | | | | |
| 8,7 | Supply and installing of toilets from approved sample with dual flush, capacity of 10 liter, rate includes seat cover with stainless steel hinges, and all accessories, all according to the work techniques and instruction of the engineer. | Piece | 2 | | | | |
| 8,8 | Supply and installing of hand wash basin complete with water mixer tap and all accessories such as drain, hoses...etc, all according to the work techniques and instruction of the engineer. | Piece | 2 | | | | |
| 8,9 | Supply and installing of water electrical heater with 80 liter capacity from approved sample, rate includes all accessories, all according to the work techniques and instruction of the engineer. | Piece | 1 | | | | |
| 8,10 | Supply and installing water tank with 3000 liter capacity made from P.V.C from approved sample, rate includes, workmanship, all accessories and fittings, pipe, valves, automatic timer, floater, all according to the work techniques and instruction of the engineer. | Piece | 1 | | | | |
| 8,11 | Supply and installing of 1 HP water centrifugal pump (SAER or DAM) or equivalent product, rate include, materials, workmanship & wiring, all according to the work techniques and instruction of the engineer. | Piece | 3 | | | | |

| | | | | | | | |
|----------------------------|--|--------------|----|--|--|--|--|
| 8,12 | supply and install of sewers with size of 15*15 cm complete with the cover, and from the approved sample for toilets sewerage and all accessories, all according to the work techniques and instruction of the engineer. | Piece | 3 | | | | |
| 8,13 | Supply and installing of 4 inch drain pipe from approved sample such as smart or red sea, to drain the sewerage from Toilets and container's TC to the existing manholes, rate shall include all needed work such as excavating, backfilling, paving & all accessories & fittings, all according to the work techniques and instruction of the engineer. | Meter Length | 20 | | | | |
| 8,14 | Supply and replacing of 2 inch drain pipe from approved sample such as smart or red sea, for toilets sewerage and rain water drain, rate shall include all accessories & fittings, all according to the work techniques and instruction of the engineer. | Meter Length | 9 | | | | |
| 8,15 | supplying and installing of heavy duty manhole covers, rate shall include all cementing works and cleaning and draining of the manhole. | Piece | 6 | | | | |
| 9- ELECTRICAL WORKS | | | | | | | |
| 9,1 | Supply and installing 12 MM crossing section of electrical copper cable according to applicable standards and specifications, rate shall include excavation, backfilling, tubing & pavement, all according to the work techniques and instruction of the engineer. | Meter Length | 24 | | | | |
| 9,2 | Supply and installing of 6 lines control panel rate shall include all necessary materials such as wiring, conduits, box, breakers...etc. from approved sample, all according to the work techniques and instruction of the engineer. | Piece | 1 | | | | |
| 9,3 | Supply and installing of 16 A single electrical switch ABB or equivalent product and for lighting controlling, replacing of the existing, all according to the work techniques and instruction of the engineer. | Piece | 6 | | | | |

| | | | | | | | |
|---|--|-------|---|---------------|--|---------------|--|
| 9,4 | Supply and installing of electrical sockets with three pins ABB or equivalent product and for lighting controlling, and replacing of the existing, all according to the work techniques and instruction of the engineer. | Piece | 6 | | | | |
| 9,5 | Supply and installing of water heaters or AC switches ABB or equivalent product and replacing of the existing, all according to the work techniques and instruction of the engineer. | Piece | 2 | | | | |
| 9,6 | Supplying and installation of fluorescent lights 4*60 w, 60 cm long complete with cover, Philips or equivalent type, rate including, all needed materials and workmanship, all according to the work techniques and instruction of the engineer. | Piece | 5 | | | | |
| 9,7 | Supplying and installation of fluorescent lights 2*60 w, 120 cm long complete with cover, Philips or equivalent type, rate including all needed materials and workmanship, all according to the work techniques and instruction of the engineer. | Piece | 6 | | | | |
| 9,8 | Supplying and installation of outdoor wall lamps complete with cover, from approval sample, rate including all needed materials and workmanship, all according to the work techniques and instruction of the engineer. | Piece | 2 | | | | |
| GRAND TOTAL (including all applicable taxes and delivery and installation) | | | | In LYD | | In USD | |

BIDDER'S COMMENTS/REMARKS:

7. _____
8. _____

DELIVERY CONDITIONS GUARANTEED BY THE BIDDER :

..... Days for 50% of completion of works
 Days for 100% of completion of works



BIDDER'S TERMS AND CONDITIONS:

- 9. Valid of the offer: _____ (recommended: 6 months for selection and contract's signature).
- 10. Terms of delivery: _____ (recommended: DDP)
- 5. Terms of payment: _____
- 6. Payments deadline: _____ days after invoice validated

Note: The offer will be submitted in English and in Libyan Dinars or USD all cost included (including delivery and installation) and taxes included.

- b. Bidders shall comply with all valid Government legal Documentation and adhere to Regulations to operate in Libya such as being regular tax payer to offer such goods and services as specified in the tender
- 5. An entity established in Libya is considered tax resident in Libya.
 - a. Any Income generated in Libya from work performed therein should be subject to income tax in Libya.
 - b. The supplier will have the obligation to provide Tax information, including handling the preparation, filing, and stamping of federal, state, or national body on the invoice of the performed service/work.

Name of Bidder's Authorized Representative: _____

Authorized signature and stamp: _____

Date: _____